

Sr.No.	Item Code
1	22-207830-0-03-ZZ-ZZ000 HSN No : SAC No : 998732
2	22-213760-C-03-ZZ-ZZ000 HSN No : SAC No : 998732
3	22-213660-C-03-ZZ-ZZ000 HSN No : SAC No : 998732
4	22-210560-0-03-ZZ-ZZ000 HSN No : SAC No : 998732
6	12-C00000-C-00-ZZ-ZZ155 HSN No : 39174000
7	22-435000-0-00-ZZ-ZZ654 HSN No : SAC No : 998732

Market rate

Item Description	UOM	Quantity	Rate	Amount
Supply & Laying of Cable,6 Sq MM, 2 Core,Copper Armoured Multi strand HRFR, Version 3.0 incldg Termination with Lugs, Saddles Cable ties, Insulation tape, Glands & other installation accessories as per Indus Standard Guidelines	Meter	47	183	8601
Supply & Laying of Cable,50 Sq MM,1 Core Red,Copper Unarmoured Multi strand Termination with Lugs, Saddles, Cable ties Insulation tape, Glands & other installation accessories, Capex	Meter	7	425	2975
Supply & Laying of Cable,50 Sq MM,1 Core Black,Copper Unarmoured Multi strand HRFR, Version 3.0 incldg Termination with Lugs Saddles, Cable ties, Insulation tape, Glands & other installation accessories, Capex	Meter	7	425	2975
Supply & Laying of Cable,16 Sq MM,1 Core Green,Copper Unarmoured Multi strand HRFR, Version 3.0 incldg Termination with Lugs, Saddles, Cable ties, Insulation tape, Glands & other installation accessories as per Indus Standard Guidelines	Meter	5	156	780
Supply & Laying of Cable,2.5 Sq MM 2 core armored cable	Meter	5	82.62	413.1
HDPE pipe 2 inch - Capex	Meter	20	50	1000
Earthing,GI strip (25x3) mm accessories,(As per Indus Standards and Guidelines)	Meter	15	85	1275
	Total			18019.1
			gst 18%	3243.438
				21262.538